


Sección Arroyo Antequera Progresiva 185.99 m. Escala: 1:250

> Volumen de Corte y Relleno del Arroyo

Antequera

Corte y Relleno - Antequera						
Estaca	Extensión	V.Corte (m³)	V.Relleno (m³)			
47,19	15,025	853,72	411,53			
77,24	33,87	900,26	964,28			
114,93	27,86	242,38	995,44			
132,96	25,86	466,26	628,14			
166,65	26,515	946,06	636,09			
185,99	21,65	433,22	523,28			
209,95	29,475	1090,58	697,08			
244,94	24,93	1721,17	808,23			
259,81	15,85	850,67	372,63			
276,64	21,495	2142,62	879,58			
302,8	30,32	735,56	715,25			
337,28	28,95	5063,36	680,33			
360,7	25,52	3569,74	598,44			
388,32	31,98	4806,59	956,52			
424,66	29,965	1852,14	693,09			
448,25	15,62	1216,80	362,23			
455,9	8,5	694,96	196,18			
465,25	4,675	233,66	107,62			
Total		27819,73	11225.95			





Título
REHABILITACION ARROYOS ANTEQUERA Y TACUARI
EXCAVACION Y RELLENO

Solicitante
Local
BID
Asunción - PY

Letra		٦	Γίρο Hoja	$\cap A$	
Е			A3	U4 <sub>/16</sub>	
20/04/2018	Ing. F. Ramírez	Ing. César López	Cambio de la geometria		
05/04/2018	Ing. F. Ramírez	Ing. César López	Estudio Inicial		
Fecha	Diseñador	Verificación	Descripción		