Sección Arroyo Antequera Progresiva 209.95 m.

**Escala: 1:250** 

Volumen de Corte y Relleno del Arroyo **Antequera** 

Corte y Relleno - Antequera						
Estaca	Extensión	V.Corte (m³)	V.Relleno (m³)			
47,19	15,025	853,72	411,53 964,28			
77,24	33,87	900,26				
114,93	27,86	242,38	995,44			
132,96	25,86	466,26	628,14			
166,65	26,515	946,06	636,09			
185,99	21,65	433,22	523,28 697,08 808,23			
209,95	29,475	1090,58				
244,94	24,93	1721,17				
259,81	15,85	850,67	372,63			
276,64	21,495	2142,62	879,58			
302,8	30,32	735,56	715,25			
337,28	28,95	5063,36	680,33			
360,7	25,52	3569,74	598,44			
388,32	31,98	4806,59	956,52			
424,66	29,965	1852,14	693,09			
448,25	15,62	1216,80	362,23			
455,9	8,5	694,96	196,18			
465,25	4,675	233,66	107,62			
Total		27819,73	11225,95			




Sección Arroyo Antequera Progresiva 244.94 m.

**Escala: 1:250** 

Volumen de Corte y Relleno del Arroyo **Antequera** 

Corte y Relleno - Antequera							
Estaca	Extensión	V.Corte (m³)	V.Relleno (m³)				
47,19	15,025	853,72	411,53				
77,24	33,87	900,26	964,28				
114,93	27,86	242,38	995,44				
132,96	25,86	466,26	628,14				
166,65	26,515	946,06	636,09				
185,99	21,65	433,22	523,28				
209,95	29,475	1090,58	697,08				
244,94	24,93	1721,17	808,23				
259,81	15,85	850,67	372,63				
276,64	21,495	2142,62	879,58				
302,8	30,32	735,56	715,25				
337,28	28,95	5063,36	680,33				
360,7	25,52	3569,74	598,44				
388,32	31,98	4806,59	956,52				
424,66	29,965	1852,14	693,09				
448,25	15,62	1216,80	362,23				
455,9	8,5	694,96	196,18				
465,25	4,675	233,66	107,62				
Total		27819,73	11225,95				





REHABILITACION ARROYOS ANTEQUERA Y TACUARI **EXCAVACION Y RELLENO** Solicitante Local

Asunción - PY

BID

Let	ra E			Típo Hoja A3	05/16
20	0/04/2018	Ing. F. Ramírez	Ing. César López	Cambio de la geometria	
05	5/04/2018	Ing. F. Ramírez	Ing. César López	Estudio Inicial	
	Fecha	Diseñador	Verificación	Descripción	