


Sección Arroyo Antequera Progresiva 276.64 m.

Escala: 1:250

Volumen de Corte y Relleno del Arroyo Antequera

Corte y Relleno - Antequera					
Estaca	Extensión	V.Corte (m³)	V.Relleno (m³)		
47,19	15,025	853,72	411,53		
77,24	33,87	900,26	964,28		
114,93	27,86	242,38	995,44		
132,96	25,86	466,26	628,14		
166,65	26,515	946,06	636,09		
185,99	21,65	433,22	523,28		
209,95	29,475	1090,58	697,08		
244,94	24,93	1721,17	808,23		
259,81	15,85	850,67	372,63		
276,64	21,495	2142,62	879,58		
302,8	30,32	735,56	715,25		
337,28	28,95	5063,36	680,33		
360,7	25,52	3569,74	598,44		
388,32	31,98	4806,59	956,52		
424,66	29,965	1852,14	693,09		
448,25	15,62	1216,80	362,23		
455,9	8,5	694,96	196,18		
465,25	4,675	233,66	107,62		
Total		27819,73	11225,95		





Título				
REHABILITACION ARROYOS ANTEQUERA Y TACUARI				
EXCAVACION Y RELLENO				
Solicitante	Local			
BID	Asunción - PY			

Letra	Típo		\cap 4
E		A3	UO _{/16}
20/04/2018 Ing. F. Rami	ez Ing. César López	Cambio de la geometria	
05/04/2018 Ing. F. Rami	ez Ing. César López	Estudio Inicial	
Fecha Diseñado	Verificación	Descripción	